



**NATIONAL AND PROVINCIAL CANADIAN CODES
ENGINEERING EVALUATION REPORT**

Issue Date	2023-12-31
Expiry Date	2024-12-31
Report Number	0084-5-1-5857
Client Name	Trex Company, Inc.
Address	2500 Trex Way, Winchester, VA 22601

Subject

Trex Transcend® Lineage™ Wood-Plastic Composite Deck Boards.

Evaluation Scope

This report is provided to assist registered design professionals and building officials in Canada with determining compliance to the performance objectives in the named building codes.

The material(s) and system(s) described herein have been evaluated to the:

- 2020 National Building Code of Canada (NBCC);**
- 2018 British Columbia Building Code (BCBC);**
- 2012 Ontario Building Code (Last Revision: May 12, 2023) (OBC);**
- 2019 National Building Code – Alberta Edition (NBC (AE));**

Division A, Sections 1.2.1.1.(1)(a)-(b) for compliance with the objectives and functional statements attributed to the applicable acceptable solutions in Division B, for buildings classified under Part 3/4/5 and Part 9 construction.

CSI DIVISION: 06 00 00 WOOD, PLASTICS, AND COMPOSITES
SUBDIVISION: 06 53 00 Plastic Decking

CODE SECTIONS AND STANDARDS: 2020 NBCC

Div. B Section	Description	Referenced Standard or Div. B Section ¹	Year
Part 3/4			
3.1.12.1.(2)	Determination of (Flame-Spread and Smoke Developed Classification) Ratings	CAN/ULC-S102.2	2018
3.8.3.2.(3)(c)	Barrier-Free Path of Travel	-	-
4.1.3.2	Strength and Stability	Table 4.1.3.2.-A	-
4.1.3.4	Serviceability	4.1.3.5, Table 4.1.3.4	-
4.1.3.5.(1)(a)	Deflection	-	-
4.1.4.1.(1)	Dead Loads	-	-
4.1.5	Live Loads Due to Use and Occupancy	Table 4.1.5.3	-
4.1.6	Loads Due to Snow and Rain	-	-
4.1.7.1.(5)(a)	Wind Load	4.1.7.3	-
4.3.1.1²	Design Basis for Wood	CSA O86	2019
4.3.1.3²	Termites	9.3.2.9	-



Part 9			
9.3.2.2 ²	Lumber Grades	Table 9.3.2.1	-
9.3.2.9.(5)(c)(i) ²	Termite and Decay Protection	CAN/CSA-O80.1	2015
9.4.1.1.(1)(c)(i)	Structural Design Requirements and Application Limits	Part 4	-
9.4.2	Specified Loads	9.4.3.1	-
9.4.2.3	Platforms Subject to Snow and Occupancy Loads	-	-
9.4.3.1	Deflections	Table 9.4.3.1	-
9.5.2.1.(1)	Barrier-Free Design, General	3.8	-
9.8.9.1	Loads on Stairs and Ramps	-	-
9.10.3.2	Flame Spread Ratings	Part 3, App. D	-
9.23.3.1.(3)	Standards for Nails and Screws	ASME B18.6.1	1981
9.30.3.1.(1) ²	Wood Strip Flooring, Thickness	Table 9.30.3.1	-

1. Only the applicable reference standards and code sections cited in the main body text are listed. (-) indicates that the main body text covers the full explanation of the objective.
2. Alternative solution evaluation completed for these code sections. See Attachment 3 for discussion of methodology.

COMPLIANCE STATEMENT:

It is the opinion of Boca Engineering Co. that Trex Transcend® Lineage™ Wood-Plastic Composite Deck Boards, when installed as described in this report, has demonstrated compliance with the listed sections of the named building codes. Design and performance information can be found in the Product Evaluation section this report.

This report has been prepared and reviewed on behalf of Boca Engineering Co. by:

Christopher Bowness, P.Eng., P.E.

2023-12-31 2024-12-31
Issue Date Expiry Date



Province of British Columbia
Permit to Practice: 1002012



Province of Ontario



Province of Alberta
Permit to Practice Stamp in ATTACHMENT 4

EVALUATION REPORT TERMS:

1. This report is a general evaluation of the building code section requirements as identified and applies only to the samples that were evaluated. It does not imply any endorsement or warranty, nor that the signatory Engineer is the Designer of Record of any construction project for which the information is used.
2. This Evaluation Report expires Dec. 31, 2024 open to renewal. Up to the renewal date, the report is valid until such time as the named product(s) changes, the Quality Assurance Agency changes, or provisions of the Code that relate to the product change.

CERTIFICATION OF INDEPENDENCE:

1. Boca Engineering Co., its employees and shareholders, do not have, nor do they intend to or will acquire, a financial interest in any company manufacturing or distributing products that they evaluate.
2. Boca Engineering Co. is not owned, operated or controlled by any company manufacturing or distributing products that they evaluate.



CONTENTS:	PAGE:
Product Evaluation.....	3
Attachments.....	8
ATTACHMENT 1: MATERIAL PROPERTIES	8
ATTACHMENT 2: ASSEMBLY DIAGRAMS	8
ATTACHMENT 3: DISCUSSION OF LIMIT STATES DESIGN PROCEDURE	11
ATTACHMENT 4: NATIONAL TO PROVINCIAL CODE CROSS-REFERENCES	13
BRITISH COLUMBIA: 2018 BCBC	13
ONTARIO: 2012 OBC (Last Revision: May 12, 2023)	14
ALBERTA: 2019 NBC (AE)	15

Product Evaluation

1.0 PRODUCT DESCRIPTION:

Trex Transcend® Lineage™ deck boards are composed of a recycled low-density polyethylene (LDPE) and wood fiber composite. The plank profile is nominal 1 inch by 5.5 inch (25 mm x 140 mm), in lengths of 12, 16 and 20 ft (3.7, 4.9, and 6.1 m), weighing 1.9 lb/ft length (2.8 kg/m), with top surface finish of an embossed simulated wood-grain pattern. The bottom surface is flat, and side edges are either flat or grooved to fit hidden fasteners.

Deck boards are supplied in a variety of colours, and are intended for use as a walking surface on exterior decks, balconies, porches, and walkways, including stairs.

1.1 MATERIAL PROPERTIES:

The materials properties of Trex Transcend® Lineage™ deck boards, tested as per ASTM D7032, *Standard Specification for Establishing Performance Ratings for Wood-Plastic Composite and Plastic Lumber Deck Boards, Stair Treads, Guards, and Handrails*, are provided in ATTACHMENT 1: MATERIAL PROPERTIES of this report.

2.0 INSTALLATION:

- 2.1 Manufacturer’s published installation instructions are available online at: <https://www.trex.com/trex-owners/customer-support/downloads/#productinstall>.
- 2.2 Manufacturer’s installation instructions, building code, and additional details in this report are to be followed.

3.0 CODE SECTIONS REVIEW:

<u>NBCC Div. B</u>	<u>Description</u>
<u>Section</u>	

Part 3/4

3.1.12.1.(2) Determination of (Flame-Spread and Smoke Developed Classification) Ratings

Trex Transcend® Lineage™ deck boards have been tested to CAN/ULC S102.2 and received a flame-spread rating of 49.

Comparable use materials in NBCC App D Tables D-3.1.1.-A & B, with an assigned flame-spread rating:
Lumber: 150; Hardwood or Softwood Flooring: 300

Flame-spread rating of 49 is equal to or better than that of the comparable materials.

Deck boards are for exterior use only, therefore the smoke developed index is regarded as not applicable.



3.8.3.2.(3)(a) &(c) Barrier-Free Path of Travel

Requires that exterior walking surfaces that are within a barrier-free path of travel to “have no opening that will permit the passage of a sphere more than 13 mm in diameter.” When used for the intended purposes stated in the installation and limitations sections of this report, the gaps between the Trex Transcend® Lineage™ deck boards do not exceed 13 mm.
Calls for exterior walking surfaces within barrier-free path of travel to be “stable, firm and slip-resistant.” Trex Transcend® Lineage™ deck boards installed under specified loads as described in this report meet the deflection limits of NBCC 4.1.3.5.(1)(a), to satisfy the requirements of this Code section. As discussed further in section 4.0 LIMITATIONS of this report, the Trex Transcend® Lineage™ deck boards have not been tested for slip resistance.

4.1.3.2 Strength and Stability

Design service live load capacity of the deck boards is maximum 100 psf (4.8 kPa) @ 16-inch (405-mm) o/c supports.^{1, 2, 3}

Design non-factored wind uplift pressure capacity of the deck boards is maximum 148 psf (7.1 kPa) @ 16-inch (405-mm) o/c supports.

Span (in, mm)	Transcend® Lineage™ Deck Boards Maximum Live Load (psf, kPa)		
	Deflection Limit		
	L/180	L/240	L/360
16 in	100 psf	100 psf	100 psf
405 mm	4.8 kPa	4.8 kPa	4.8 kPa

1. Calculated using the published strength and stiffness values in Table 1 of this report, deck board spanning and secured to a minimum of three supports, applying an L/240 live load deflection limit, and a total dead load of 0.5 kPa. See table for other load and deflection limit values.

2. Other loading conditions limits may be calculated using the materials values published in Table 1 of this report.

3. Deck boards tested in manner intended for use were subjected to maximum compression and shear forces for loading condition, where bending strength and deflection were shown to be the governing limit states.

The load combinations in NBCC Table 4.1.3.2.-A that are applicable to the use of this product are those with Dead, Live, Wind, and Snow.

The allowable strength capacity of Trex Transcend® Lineage™ deck boards is published as the tested ultimate strength values adjusted for reductions due to temperature and moisture effects, with a safety factor of 2.5. The 2.5 factor may be regarded as the limit states load factor divided by the resistance factor.

4.1.3.4 Serviceability

Serviceability considerations of deflection under load, long-term durability and creep have been evaluated through testing, as reported in ATTACHMENT 1: MATERIAL PROPERTIES of this report.

4.1.3.5.(1)(a) Deflection

The deflection limit of L/180 (0.09-inch [2.2 mm] @ 16-inch span) @ 100 psf (4.8 kPa) live load is in conformance with CSA 086 clause 5.4.2.



- 4.1.4.1.(1) Dead Loads**
Dead load of Trex Transcend® Lineage™ deck board material weight and accessories may be taken as 5.0 psf (0.24 kPa).
- 4.1.5 Live Loads Due to Use and Occupancy**
Live loads for occupancy use are found in NBCC Table 4.1.5.3. Deck board applications live loads range from 1.9 to 4.8 kPa.
- 4.1.6 Loads Due to Snow and Rain**
The maximum design snow and rain load is 100 psf (4.8 kPa) @ 16-inch (405 mm) o/c supports. Per NBCC 4.1.5.5.(3), design live load of exterior pedestrian areas is taken as the greater of the occupancy live load or snow and rain load, not combined.
- 4.1.7.1.(5) Wind Load**
(a) The maximum design wind uplift pressure for the deck boards is 148 psf (7.1 kPa). Specified wind pressure of secondary structural members is found by the static procedure equation in NBCC 4.1.7.3.
- 4.3.1.1 Design Basis for Wood**
Trex Transcend® Lineage™ deck boards have been compared to those of materials in CSA O86, *Engineering Design in Wood*, and are found to perform as a suitable alternate for those materials when used for the intended purposes stated in the installation and limitations sections of this report. The alternative solution methodology is further discussed in Attachment 3.
- 4.3.1.3 Termites**
Refers to article 9.3. See this report commentary to NBCC 9.3.2.9.
- Part 9**
- 9.3.2.2 Lumber Grades**
Trex Transcend® Lineage™ deck boards have been compared to those of materials in NLGA 2017, *Standard Grading Rules for Canadian Lumber*, and are found to perform as a suitable alternate for those materials when used for the intended purposes stated in the installation and limitations sections of this report. The alternative solution methodology is further discussed in Attachment 3.
- 9.3.2.9.(5)(c) Termite and Decay Protection**
(i) Trex Transcend® Lineage™ deck boards have been tested for decay and termite resistance and found to perform as well as pressure-treated Pine lumber in accordance with CAN/CSA-O80.1 for UC3.2 exterior construction.
- 9.4.1.1.(1)(c) Structural Design Requirements and Application Limits**
(i) The design methodology in this evaluation for determining conformance to Part 9 has been performed in accordance with NBCC 9.4.1.1.(1)(c)(i) using the loads and deflection limits specified in Part 9.
- 9.4.2 Specified Loads**
See this report commentary to NBCC 9.4.2.3.



9.4.2.3 Platforms Subject to Snow and Occupancy Loads

See this report commentary to NBCC 4.1.3.2 for design load and deflection limits. The exterior balcony occupancy floor load in Part 9 is generally 1.9 kPa. Where exterior balconies are subject to snow loads, the greater of floor or snow load is to be used as the design load.

9.4.3.1 Deflections

The deflection limits of NBCC Table 9.4.3.1 are met for applicable loading conditions. See this report commentary to NBCC 9.4.2.3.

9.5.2.1.(1) Barrier Free Design, General

Refers to NBCC Section 3.8. See this report commentary to NBCC 3.8.3.2.(3)(a)&(c).

9.8.9.1 Loads on Stairs and Ramps

The installation of Trex Transcend® Lineage™ deck boards at 16-inch (405-mm) span meets the strength and serviceability requirements for stairs at uniform loads of 1.9 kPa and 4.8 kPa. For improved serviceability, when installed as plank stair treads, it is recommended to use the design criteria of ASTM D7032, with supports spanned at maximum 12 inches (305 mm) to limit the deflection of a 300-lb (1.3 kN) point load at centre-span to ¼-inch (6.4 mm).

9.10.3.2 Flame Spread Ratings

Refers to test methods in Part 3 and Appendix D. See this report commentary to NBCC 3.1.12.1.(2).

9.23.3.1.(3) Standards for Nails and Screws

Deck screws supplied by Trex for hidden fastening comply with ASME B18.6.1.

9.30.3.1.(1) Wood Strip Flooring, Thickness

The nominal thickness of Trex Transcend® Lineage™ deck boards meet NBCC Table 9.30.3.1 for exterior-use softwood lumber. The Trex materials are found to perform as well as a natural wood plank such as SPF No. 2 lumber for the intended purposes within the limitations of this report.

4.0 LIMITATIONS:

1. This Evaluation is for the base code requirements of the building system as addressed in this report. In some building applications, additional performance objectives may be required by Code which must be addressed in the building design for those specific cases.
2. Design calculations, drawings, and special inspections are to be furnished for building projects by registered professionals as required by the respective jurisdictional authorities and Codes.
3. Deck boards are to be installed with a minimum width-to-width gap of $\frac{3}{16}$ inch (4.8 mm), and end-to-end gap of $\frac{1}{8}$ inch (3.2 mm) if installed at greater than 4.5°C or $\frac{3}{16}$ inch (4.8 mm) if installed at less than 4.5°C, to allow for drainage and linear expansion of framing materials.
4. Deck boards are not for use as bracing against lateral (wind or seismic) loads.
5. Products are for exterior use only.
6. Products are to be used as exterior deck flooring planks only. No other functions of lumber materials used in buildings are addressed in this evaluation.
7. Strength and performance values apply to temperature at deck surface ranging from -29°C to 52°C.



8. Deck boards are to be fastened to wood framing built in conformance to NBCC Part 4 or Part 9 using corrosion resistant #7 screws supplied by Trex or jobsite supplied min. #8 wood deck screws complying with ASME B18.6.1.
9. The product is to be installed perpendicular to supports spaced no greater than 16 inch (405 mm) on center. Each plank is to span across at least three supports.
10. Installation directly to underfloor sheathing is not permitted. When installing over solid deck sheathing, sleepers of a minimum true dimension of 1.5 inch x 1.5 inch (38 mm x 38 mm) to be placed and fastened to framing, beneath as deck board supports, at maximum 16 inch (405 mm) on center perpendicular to deck boards.
11. The scope of this evaluation does not include slip resistance. Trex Transcend® Lineage™ deck boards have not been tested to ASTM F1679, *Standard Test Method for Using a Variable Incidence Tribometer*, a slip resistance test referenced in ASTM D7032.

5.0 FIRE CLASSIFICATION:

Summary of fire performance classifications found by testing to code referenced standards:

Combustible: Trex Transcend® Lineage™ deck boards are a *combustible* material as defined in NBCC, Div A, 1.4.1.2. CAN/ULC S102.2: Flame Spread Index of 49.

6.0 QUALITY ASSURANCE ENTITY:

The products evaluated in this report are surveyed at the approved manufacturing locations with third-party quality assurance inspections and product certification labeling by QAI Laboratories, Inc.

7.0 MANUFACTURING PLANTS:

Manufacturing and labeling location(s): Winchester, VA; Fernley, NV.

8.0 LABELING:

Labeling shall be in accordance with the requirements of and bear the certification mark of the Accredited Quality Assurance Agency.

9.0 REFERENCE TESTING AND EVALUATION DOCUMENTS:

Entity	Entity Accreditation ¹	Standards	Report No.	Issue Date
Intertek	IAS TL 144	ASTM D6109, D7032, D7031, E330	I5750.01-119-19	2018-Sep-06
Intertek	IAS TL 144	ASTM D790, D2565, D6109, D7032	N2941.01-119-19	2022-Jul-12
Intertek	IAS TL 144	ASTM D695	K1513.04-106-31	2019-Dec-09
QAI Laboratories	IAS TL 220	CAN/ULC S102.2	RJ8682F-5	2022-Oct-04
QAI Laboratories	SCC 10024	Quality Assurance	B1109-1	2023-Dec-31

1. Testing, certification, evaluation, and inspection agencies referenced have been verified to be accredited by Standards Council of Canada (www.scc.ca) or International Accreditation Service (www.iasonline.org) for the applicable scope, in good standing on the date of the evaluation, in accordance with ISO 17025 and ISO 17020 international standards for testing and inspection bodies.



Attachments


ATTACHMENT 1: MATERIAL PROPERTIES

TABLE 1: TREX TRANSCEND® LINEAGE™ DECK BOARDS, MATERIALS PROPERTIES PER ASTM D7032				
D7032 Section	Property	Requirement	Value	
4.4.1	Flexural Strength Moment Capacity (M_u)	Report Value	3160 in-lb (0.3570 kN-m)	
4.4.2	Flexural Stiffness (EI)	Report Value	198,100 lb-in ² (0.5685 kN-m ²)	
4.5.1	Temperature Effect	Report % change of strength and stiffness @ 52°C & -29°C	Strength (52°C):	-33%
			Stiffness (52°C):	-43%
			Strength (-29°C):	0%
			Stiffness (-29°C):	0%
4.5.2	Moisture Effect	Report strength adjustments after water saturation	0% water absorption, 0% adjustments	
4.6	Ultraviolet (UV) Effect	Report % increase/decrease of strength and stiffness after 2000 hrs of accelerated weathering	Strength:	-4%
			Stiffness:	-7%
4.7	Freeze-Thaw Effect	Report % change of strength and stiffness after three 24-hr freezing cycles @ -29°C	Strength:	+4%
			Stiffness:	0%
4.8.1	Fungal Decay Resistance	Compare test block per AWWA E10 to ACQ pressure-treated lumber	Performed equivalent to ACQ-treated Pine	
4.8.2	Termite Decay Resistance	Compare test block per ASTM D3345 to ACQ pressure-treated lumber	Performed equivalent to ACQ-treated Pine	
4.9	Surface Burning Characteristics ¹	Flame-spread index no greater than 200	49	
5.3.1	Determination of Allowable Service Loads	Design strength and stiffness service values after climate adjustment factors, with strength safety factor of 2.5 applied	Moment Strength ($M_{SERVICE}$):	847 lb-in (0.0957 kN-m)
			Stiffness ($EI_{SERVICE}$):	112,917 lb-in ² (0.3241 kN-m ²)
5.3.2	Concentrated (Stair tread) Load	Deflection < 0.125" @ 300 lbf, and ultimate > 750 lbf	12" span, $\Delta = 0.0760"$, Ult = 1197 lbf Meets requirements	
5.4	Creep-Recovery Test	2x 100 psf design load for 24 hrs, min 75% deflection recovery	89% Recovery Meets requirements	
5.5	Mechanical Fastener Holding Test ²	Report value of fastener pull-through of the deck board, and withdrawal from framing substrate, with strength safety factor of 3 applied	Pull-Through:	180 lbf / screw
			Withdrawal:	195 lbf / screw
Add. Tests	Wind Uplift	System maximum uplift design pressure, tested by ASTM E330-02, with safety factor of 3 applied	148 psf (7.1 kPa) maximum uplift pressure at 16 inch (405 mm) maximum span	
	90-day Load Duration	2x 100 psf design load for 90-days, per ASTM D7031, no evidence of tertiary creep	No evidence of tertiary creep Meets requirements	
	Compressive Strength (psi)	Design compressive strength per ASTM D695 service values after climate adjustment factors, with strength safety factor of 2.5 applied	585 psi (4.03 MPa)	


- CAN ULC/S102.2 test results substituted for ASTM E84 test.
- Mechanical Fastener Holding Test values are obtained from the Enhance 2.0 ASTM D7032 test report I5515.01-119-19 by Intertek. The flexural strength, stiffness, wind uplift resistance, and compressive strength values for Transcend are greater than Enhance deck boards; therefore, it can be concluded that the Mechanical Fastener Holding test will perform equal or better than the Enhance test results.

ATTACHMENT 2: ASSEMBLY DIAGRAMS


Begins next page.



A
1 TYP. TREX HIDDEN FASTENER INSTALLATION
NOT-TO-SCALE





B
1 TYP. CONSTRUCTION FASTENER INSTALLATION
NOT-TO-SCALE



C
1 TYP. TREX DECK BOARD ASSEMBLY - PLAN
NOT-TO-SCALE

COPYRIGHT © 2023 RESERVED. THESE PLANS AND DESIGNS ARE AT ALL TIMES THE PROPERTY OF BOCA ENGINEERING TO BE USED FOR THE PROJECT SHOWN. WRITTEN CONSENT IS REQUIRED FROM THE ENGINEER BEFORE ANY REPRODUCTION.

BOCA ENGINEERING CO. SPAR STRUCTURAL & CIVIL CONSULTANTS	CLIENT TREX COMPANY, INC.		PROJECT TREX TRANSCEND LINEAGE DECK BOARDS			
	DATE DECEMBER 31, 2023		REV. 0	FOR PUBLICATION		CB
	DRAWING NO. 0084-5857-SK1		SHEET NO. 1 OF 2		SCALE NOT TO SCALE	DES. DRN. CHK. CB TH CB
	DRAWING FOR ENGINEERING EVALUATION REPORT - NOT FOR USE AS CONSTRUCTION DESIGN DOCUMENTS					




A
2 TRANSCEND LINEAGE 1x6 SQUARE EDGE BOARDS
NOT-TO-SCALE

B
2 TRANSCEND LINEAGE 1x6 GROOVED EDGE BOARDS
NOT-TO-SCALE

DESIGN LOADS	
LIVE (DECK)	SEE EVALUATION REPORT
SNOW	
WIND	
SEISMIC	
TEMPERATURE	

LEGEND AND SYMBOLS



INSTALLATION

- FOR COMPLETE INSTALLATION DETAILS SEE TECHNICAL PRODUCT DATA ON PRODUCT MANUFACTURE'S WEBSITE.

MATERIAL STANDARDS

SHEATHING

- WOOD-BASED STRUCTURAL SHEATHING:
 - PLYWOOD - CSA 0121-17, CSA 0151-17 OR CSA 0153-13
 - OSB - CSA 0437.0-93
 - LUMBER - CSA 0141-05

- GYPHUM SHEATHING: ASTM C1396-17, EXTERIOR TYPE

FASTENERS

- WOOD SCREWS: ASME B18.6.1-81(2016)
- NAILS: ASTM F1667-18A
- METAL SCREWS: AISI S240-15, ASTM C1513-13
- ALL FASTENERS CORROSION-RESISTANT OR STAINLESS STEEL

FRAMING

- WOOD FRAMING: MIN. 2x4 S.G. 0.42, COMPLIANCE WITH CSA 0141-05
- METAL FRAMING: MIN. 18 GAUGE U.N.O., $F_y = 33\text{ksi}$, COMPLIANCE WITH CSA S136-16

ABBREVIATIONS

CONT	CONTINUOUS	O.C.	ON CENTER
EA	EACH	P.T.	PRESSURE TREATED
E/W	EACH WAY	S.G.	SPECIFIC GRAVITY
EXT.	EXTERIOR	SPEC.	SPECIFICATION
INT.	INTERIOR	NO.	TYPICAL
MAX	MAXIMUM	U.N.O.	UNLESS NOTED OTHERWISE
MIN	MINIMUM	W/	WITH
NO.	NUMBER		

DESIGN

- STRUCTURAL WORK HAS BEEN DESIGNED IN ACCORDANCE WITH APPLICABLE CODES AND STANDARDS REFERENCED IN THE EVALUATION REPORT.
- THE STRUCTURAL FRAMING AND SHEATHING SHALL BE DESIGNED AND ANCHORED TO PROVIDE LATERAL BRACING AND PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. FRAMING DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- THESE DRAWINGS APPLY TO THE TESTED ASSEMBLY ONLY AND DO NOT IMPLY THAT THE SIGNATORY ENGINEER IS THE DESIGNER OF RECORD FOR ANY FUTURE CONSTRUCTION ON WHICH THEY ARE USED.
- SOME NON-STRUCTURAL COMPONENTS NOT SHOWN AND DO NOT IMPACT STRENGTH FOR ATTACHMENT. TO BE INSTALLED PER CODE AND MAY INCLUDE: FLASHING, INSULATION, INTERIOR FINISH.

INSPECTIONS (FIELD REVIEWS)

- NOTIFICATION FOR INSPECTIONS AND INSTALLATION APPROVAL SHOULD BE COMPLETED AS OUTLINED BY ANY OF THE FOLLOWING APPLICABLE TO THE REFERENCED PROJECT:
 - APPLICABLE LOCAL BUILDING CODE.
 - LOCAL BUILDING AUTHORITY.
 - PROJECT SPECIFICATION DOCUMENTS BY OTHERS.
- FIELD REVIEWS OF INSTALLATION ARE NOT COMPLETED BY THE EVALUATION REPORT ENGINEER.

TESTING AND CODE COMPLIANCE

- THE PRODUCT ASSEMBLY SHOWN HAS BEEN EVALUATED ACCORDING TO THE TEST STANDARDS AS OUTLINED IN THE EVALUATION REPORT.
- THE INSTALLATION DETAILS DESCRIBED ARE OF THE LABORATORY TESTED ASSEMBLY AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, THE LICENSED ENGINEER OR ARCHITECT PREPARED SITE-SPECIFIC DOCUMENTS SHALL BE USED.

COPYRIGHT © 2023 RESERVED. THESE PLANS AND DESIGNS ARE AT ALL TIMES THE PROPERTY OF BOCA ENGINEERING TO BE USED FOR THE PROJECT SHOWN. WRITTEN CONSENT IS REQUIRED FROM THE ENGINEER BEFORE ANY REPRODUCTION.

TITLE	CLIENT	PROJECT			
TREX DECK BOARD PROFILES & GENERAL NOTES	TREX COMPANY, INC.	TREX TRANSCEND LINEAGE DECK BOARDS			
BOCA ENGINEERING CO. SPAR STRUCTURAL & CIVIL CONSULTANTS	DATE	REV.	FOR PUBLICATION	CB	
	DECEMBER 31, 2023	0	ISSUE	APP	
	DRAWING NO.	SHEET NO.	SCALE	DES.	DRN.
0084-5857-SK1	2 OF 2	NOT TO SCALE	CB	TH	CB

DRAWING FOR ENGINEERING EVALUATION REPORT - NOT FOR USE AS CONSTRUCTION DESIGN DOCUMENTS



ATTACHMENT 3: DISCUSSION OF LIMIT STATES DESIGN PROCEDURE

Acceptable Solutions

Once the materials properties of the Trex deck boards have been established, design to prescribed performance requirements in the code can be conducted. From the perspective of meeting the requisite acceptable solutions of the in-use performance required by Code for exterior deck planks, much of this design evaluation fits within the acceptable solution methodology of Part 3/Part 4 and of Part 9, where the specific Code requirements are shown to meet the Code as-written.

Alternative Solutions - Wood-Plastic Composite (WPC) Components

The wood-plastic composite (WPC) components do not fit within a code-referenced material standard, so an alternative solution design evaluation method is employed to ensure that the material as installed meets the minimum level of performance required by Code following NBCC Div A 1.2.1.1.(1)(b).

The deck board material dimensions, constituents, installation methods, and end-use as an exterior deck plank, most closely align as an alternate for natural wood materials used for the same purpose that fall within acceptable solution materials specifications in Div B, Articles 4.3.1.1, 4.3.1.3, 9.3.2.2, 9.3.2.9.(5)(c)(i), and 9.30.3.1.(1). Article 4.3.1.1 further refers to CSA 086, *Engineering Design in Wood*, and Article 9.3.2.2 further refers to NLGA 2017 *Standard Grading Rules for Canadian Lumber*.

Appropriate published standards by organizations accredited by Standards Council of Canada have been used to complete the alternative solutions evaluation through testing and design modeling.

ASTM D7032-17, *Standard Specification for Establishing Performance Ratings for Wood-Plastic Composite and Plastic Lumber Deck Boards, Stair Treads, Guards, and Handrails*, has methods for testing the strength and deflection of deck boards inclusive of considering the effects of possible strength loss due to temperature, aging, moisture, and freeze-thaw. The deck board properties found through testing were taken through a design model using the loading requirements of NBCC Part 4 and Part 9.

Design of structural components by strength testing with a test load (safety) factor in limit states design necessitates the computation of a test load factor for the respective stress and failure type due to the various loading types. Deck plank members are typically stressed to failure in bending or in shear, depending on the placement of the test load with respect to the connection/support of the member.

Test Load Factors are computed by:

$$\text{Test Load Factor} = \frac{\text{Combined Load Factor}}{\text{Resistance Factor}}$$

ASTM D7032 recommends a safety factor (test factor) of 2.5 applied to service-level loads. In limit states design standards, a material resistance factor is typically published, which allows for computation of a test factor. When no resistance factor is available and the standard stipulates a test factor, the computation becomes of finding the



effective resistance factor. In this evaluation, the effective resistance factor for all loading/stress types is $\Phi = 0.60$.

The applicable objectives and functional statements from NBCC Div A Part 2 and 3, taken from the referenced Div B acceptable solutions, that the WPC components have been verified to satisfy are:

Objectives are to limit the risk of injury, illness, or damages, caused by:

Symbol Description

- OS2.1 Ultimate loads on building elements
- OS2.3 Damage or deterioration of building elements
- OH4 Illness attributed to vibration and deflection
- OP2.1 Loads bearing on the building elements that exceed their loadbearing capacity
- OP2.3 Damage to or deterioration of building elements
- OP2.4 Vibration or deflection of building elements

The building elements are to perform the following functions:

Symbol Description

- F20 Support and withstand expected loads
- F21 Limit dimensional change
- F22 Limit movements under expected loads and forces
- F80 Resist deterioration from expected service conditions
- F81 Minimize the risk of malfunction, interference, damage, tampering, lack of use or misuse



ATTACHMENT 4: NATIONAL TO PROVINCIAL CODE CROSS-REFERENCES

BRITISH COLUMBIA: 2018 BCBC

NBCC Div. B Section	BCBC Div. B Section	BCBC Referenced Standard or Div. B Section ¹	Year	BCBC Comparison to NBCC
Part 3/4				
3.1.12.1.(2)	3.1.12.1.(2)	CAN/ULC-S102.2	2010	Article content same, referenced standard year differs
3.8.3.2.(3)(a)(c)	3.8.3.2.(2)(a)(c)	3.8.3.6	-	Article content same as NBCC
4.1.3.2	4.1.3.2	Table 4.1.3.2.-A	-	Article content same as NBCC
4.1.3.4	4.1.3.4	4.1.3.5	-	Article content same as NBCC
4.1.3.5.(1)(a)	4.1.3.5.(1)(a)	-	-	Article content same as NBCC
4.1.4.1.(1)	4.1.4.1.(1)	-	-	Article content same as NBCC
4.1.5	4.1.5	Table 4.1.5.3	-	Article content same as NBCC
4.1.6	4.1.6	-	-	Article content same as NBCC
4.1.7.1.(5)(a)	4.1.7.1.(5)(a)	4.1.7.3	-	Article content same as NBCC
4.3.1.1²	4.3.1.1²	CSA O86	2014	Article content same as NBCC
4.3.1.3²	4.3.1.3²	9.3.2.9	-	Article content same as NBCC
Part 9				
9.3.2.2²	9.3.2.2²	Table 9.3.2.1	-	Article content same as NBCC
9.3.2.9.(5)(c)(i)²	9.3.2.9.(5)(c)(i)²	CAN/CSA-O80.1	2008	Article content same, referenced standard year differs
9.4.1.1.(1)(c)(i)	9.4.1.1.(1)(c)(i)	Part 4	-	Article content same as NBCC
9.4.2	9.4.2	-	-	Article content same as NBCC
9.4.2.3	9.4.2.3	-	-	Article content same as NBCC
9.4.3.1	9.4.3.1	Table 9.4.3.1	-	Article content same as NBCC
9.5.2.1.(1)	9.5.2.1.(1)	3.8	-	Article content same as NBCC
9.8.9.1	9.8.9.1	-	-	Article content same as NBCC
9.10.3.2	9.10.3.2	Part 3, App. D	-	Article content same as NBCC
9.23.3.1.(3)	9.23.3.1.(3)	ASME B18.6.1	1981	Article content same as NBCC
9.30.3.1.(1)²	9.30.3.1.(1)²	Table 9.30.3.1	-	Article content same as NBCC

1. Only the applicable reference standards and code sections cited in the main body text are listed. (-) indicates that the main body text covers the full explanation of the objective.
2. Alternative solution evaluation completed for these code sections. See Attachment 3 for discussion of methodology.



ONTARIO: 2012 OBC (Last Revision: May 12, 2023)

NBCC Div. B Section	OBC Div. B Section	OBC Referenced Standard or Div. B Section ¹	Year	OBC Comparison to NBCC
Part 3/4				
3.1.12.1.(2)	3.1.12.1.(2)	CAN/ULC-S102.2	2010	Article content same, referenced standard year differs
3.8.3.2.(3)(a)(c)	3.8.1.3.(2)(a)(c)	-	-	Article content same as NBCC
4.1.3.2	4.1.3.2	Table 4.1.3.2.-A	-	Article content same as NBCC
4.1.3.4	4.1.3.4	4.1.3.5	-	Article content same as NBCC
4.1.3.5.(1)(a)	4.1.3.5.(1)(a)	-	-	Article content same as NBCC
4.1.4.1.(1)	4.1.4.1.(1)	-	-	Article content same as NBCC
4.1.5	4.1.5	Table 4.1.5.3	-	Article content same as NBCC
4.1.6	4.1.6	-	-	Article content same as NBCC
4.1.7.1.(5)(a)	4.1.7.1.(5)(a)	4.1.7.3	-	Article content same as NBCC
4.3.1.1 ²	4.3.1.1 ²	CSA O86	2014	Article content same, referenced standard year differs
4.3.1.3 ²	4.3.1.3 ²	9.3.2.9	-	Article content same as NBCC
Part 9				
9.3.2.2 ²	9.3.2.2 ²	Table 9.3.2.1	-	Article content same as NBCC
9.3.2.9.(5)(c)(i) ²	9.3.2.9.(6)(c)(i) ²	CAN/CSA-O80.1	2008	Article content same, referenced standard year differs
9.4.1.1.(1)(c)(i)	9.4.1.1.(1)(c)(i)	Part 4	-	Article content same as NBCC
9.4.2	9.4.2	-	-	Article content same as NBCC
9.4.2.3	9.4.2.3	-	-	Article content same as NBCC
9.4.3.1	9.4.3.1	Table 9.4.3.1	-	Article content same as NBCC
9.5.2.1.(1)	9.5.2.1.(1)	3.8	-	Article content same as NBCC
9.8.9.1	9.8.9.1	-	-	Article content same as NBCC
9.10.3.2	9.10.3.2	Part 3, App. D	-	Article content same as NBCC
9.23.3.1.(3)	9.23.3.1.(3)	ASME B18.6.1	1981	Article content same as NBCC
9.30.3.1.(1) ²	9.30.3.1.(1) ²	Table 9.30.3.1	-	Article content same as NBCC


1. Only the applicable reference standards and code sections cited in the main body text are listed. (-) indicates that the main body text covers the full explanation of the objective.
2. Alternative solution evaluation completed for these code sections. See Attachment 3 for discussion of methodology.



ALBERTA: 2019 NBC (AE)

NBCC Div. B Section	BCBC Div. B Section	BCBC Referenced Standard or Div. B Section ¹	Year	BCBC Comparison to NBCC
Part 3/4				
3.1.12.1.(2)	3.1.12.1.(2)	CAN/ULC-S102.2	2010	Article content same, referenced standard year differs
3.8.3.2.(3)(a)(c)	3.8.3.2.(2)(a)(c)	-	-	Article content same as NBCC
4.1.3.2	4.1.3.2	Table 4.1.3.2.-A	-	Article content same as NBCC
4.1.3.4	4.1.3.4	4.1.3.5	-	Article content same as NBCC
4.1.3.5.(1)(a)	4.1.3.5.(1)(a)	-	-	Article content same as NBCC
4.1.4.1.(1)	4.1.4.1.(1)	-	-	Article content same as NBCC
4.1.5	4.1.5	Table 4.1.5.3	-	Article content same as NBCC
4.1.6	4.1.6	-	-	Article content same as NBCC
4.1.7.1.(5)(a)	4.1.7.1.(5)(a)	4.1.7.3	-	Article content same as NBCC
4.3.1.1 ²	4.3.1.1 ²	CSA O86	2014	Article content same, referenced standard year differs
4.3.1.3 ²	4.3.1.3 ²	9.3.2.9	-	Article content same as NBCC
Part 9				
9.3.2.2 ²	9.3.2.2 ²	Table 9.3.2.1	-	Article content same as NBCC
9.3.2.9.(5)(c)(i) ²	9.3.2.9.(5)(c)(i) ²	CAN/CSA-O80.1	2008	Article content same, referenced standard year differs
9.4.1.1.(1)(c)(i)	9.4.1.1.(1)(c)(i)	Part 4	-	Article content same as NBCC
9.4.2	9.4.2	-	-	Article content same as NBCC
9.4.2.3	9.4.2.3	-	-	Article content same as NBCC
9.4.3.1	9.4.3.1	Table 9.4.3.1	-	Article content same as NBCC
9.5.2.1.(1)	9.5.2.1.(1)	3.8	-	Article content same as NBCC
9.8.9.1	9.8.9.1	-	-	Article content same as NBCC
9.10.3.2	9.10.3.2	Part 3, App. D	-	Article content same as NBCC
9.23.3.1.(3)	9.23.3.1.(3)	ASME B18.6.1	1981	Article content same as NBCC
9.30.3.1.(1) ²	9.30.3.1.(1) ²	Table 9.30.3.1	-	Article content same as NBCC

1. Only the applicable reference standards and code sections cited in the main body text are listed. (-) indicates that the main body text covers the full explanation of the objective.
2. Alternative solution evaluation completed for these code sections. See Attachment 3 for discussion of methodology.



Permit to Practice